Drinking Fountain

C.B. Type "A" Inv.=

C.B. Type "B" Inv.=309.0

C.B. Type "B" Inv.=306.5

M.H. Inv.=306.5

C.B. Type "B" Inv.=307.4

18 Slab Lev.=314.6

16 Slab Lev.=312.5

15 Slab Lev.=312.5

Drip pot to be furnished & installed by S.C. Electric and Gas Co.

C.B. Type "B" Inv.=302.4

Existing M.H. Rim=301.52 Inv.=296.91

Existing M.H. Rim=310.39 Inv.=308.44

C.B. Type "A" C.B. Type "A"

Catch basins and connections to new storm sewer to be installed by the City of Columbia, S.C.

Existing M.H. Rim=309.45 Inv.=304.08

M.H. Inv.=304.22

M.H. Inv.=305.64

C.B. Type "B" Inv.=312.1

12 Slab Lev.=318.5

14 Slab Lev.=317.6

22 Slab Lev.=316.75

Drip pot to be furnished and installed by the S.C. Electric and Gas Co.

C.B. Type "A" Inv.=318.44

C.B. Type "B" Inv.=316.9

C.B. Type "B" Inv.=318.1

C.B. Type "B" Inv.=315.2

13 Slab Lev.=325.5

24 Slab Lev.=323.5

17 Slab Lev.=321.5

C.O. Inv.=319.6

C.O. Inv.=319.0

C.O. Inv.=319.7

C.O. Inv.=319.6

C.O. Inv.=321.2

M.H. Inv.=319.0

M.H. Inv.=318.7

M.H. Inv.=316.6

Existing Fire Hydrant

Established Property Line

Sidewalk

Washington Street

This storm sewer to be installed by the City of Columbia, S.C.

Contractor to connect storm sewer to manhole to be constructed by the City of Columbia, S.C. at this point.

Fire hydrant to be installed by the City of Columbia, S.C.

3" Water Meter to be installed by the City of Columbia, S.C. but paid for by the Contractor.

Contractor to connect storm sewer to manhole to be constructed by the City of Columbia, S.C. at this point.

This water main to be installed by the City of Columbia, S.C.

Marshall Street

McDuffie Avenue

Existing Fire Hydrant

Property Line as purchased by the local Housing Authority

Center Line

Existing M.H. Rim=301.52 Inv.=296.91

S 8.03 %

Note

Details of Manhole Castings and Construction as shown on this sheet are standard for the City of Columbia

Plan of Manhole Casting
Scale ¼ inch = 1 inch

Approximate Weight of Manhole=1901bs

Section of Manhole Casting
Scale ¼ inch = 1 inch.

Plan of Under Side of Manhole Cover
Scale ¼ inch = 1 inch

Approximate Weight of Cover= 136½ lbs.

Plan of Top of Manhole Cover
Scale ¼ inch = 1 inch

Half-Section Thru Manhole Cover
Scale ½ inch = 1 inch

Section

Section

Storm Water Manhole

Outlet Pipe

Plan and Sections of Manholes
Scale ½" = 1 foot

Depth of Manhole Varies

Steps

Sanitary Sewer Manhole

Cement Mortar

½" Cement Mortar

Step

Top of pipe cut away to form invert (Sanitary Sewer Manhole)

NOTES—

All sanitary sewers from buildings to mains to be 4".

For existing utilities see Plan No.3, Utility Map.

For other finished grade elevations see Block Plans.

Design of streets, driveways, paving, curbing and walks dedicated for public use and layout of all utilities in public rights of way are hereby approved by the City of Columbia, S.C.

W.S. Tomlinson, City Engineer.

· FOREST DRIVE ·

· LYON STREET · · WASHINGTON STREET · · McDUFFIE AVE ·

· KEY PLAN ·

SHEET TITLE: PLAN OF BLOCK "C" — SANITARY & STORM SEWERS, WATER LINES AND GAS LINES.

GONZALES GARDENS
LOW RENT HOUSING PROJECT, COLUMBIA, S. C. 2-1
DEVELOPED BY
THE HOUSING AUTHORITY OF THE CITY OF COLUMBIA, S. C.
UNDER LOAN CONTRACT WITH
UNITED STATES HOUSING AUTHORITY

CHECKED: — APPROVED BY: UNITED STATES HOUSING AUTHORITY — SCALES: 1/20 = 1'-0"

DATE: 9-18-39 — ADMINISTRATOR — DATE

REVISIONS:

APPROVED BY: THE HOUSING AUTHORITY OF THE CITY OF COLUMBIA, S. C.
CHAIRMAN — DATE 9-15-39
JAMES B. GROUHART, CONSULTING ARCHITECT, COLUMBIA, S. C.
ARCHITECT — DATE 9-15-39

SHEET No. OP 1613

Tomlinson Engineering Co. Columbia, S.C. Engineers